



കേരളം KERALA

DZ 315975

AGREEMENT NO 93 AEE(ELE)/2024-2025 FOR WORKS

Contract agreement entered into this 28th day of September Two thousand and twenty-Four. Sri, Pradeepkumar.P Panamvila veedu,, Peroor Thattarkonam Kollam, , of the one part and the Assistant Executive Engineer, PWD Electrical Sub Division, Kollam for and on behalf of the Governor of Kerala of the other part for the work: "MP-LADS-2022-23, Work proposed by Sri. N.K Premachandran M.P(LS), Construction of Building for Brothers Library and Reading Room-Puthenchantha at Panmana Gramapanchayat in Chavara Constituency-General Electrical Work" by the former for the use of the Public works Department of the Said Government of the State of Kerala as per accompanying agreements, plans, specifications and conditions of contract approved by the Assistant Executive Engineer, PWD Electrical Sub Division, Kollam.

Signed and delivered by the above mentioned.

Signed and delivered by Smt. Sindhu P, Assistant Executive Engineer, PWD Electrical Sub Division, Kollam
for and on behalf of the Governor of Kerala.

In the Presence of Witnesses:

1. Ajiro CA, FGO *[Signature]*
2. Meibam Ramesh R. SGO, *[Signature]*

Contractor

[Signature]
Sindhu P

Assistant Executive Engineer
PWD Electrical Sub Division
Kollam

For and on behalf of the Governor of Kerala

[Signature]
K. AMBILI
STAMP VER NO.
K. KOLLAM

No. 8696 101-
12-10-2023

ചേരിപിള്ള
ചാക്കംവിളമ്പി
ചേട്ടൻ.

AGREEMENT SCHEDULE

Name of Work: MP-LADS-2022-23, Work proposed by Sri. N.K Premachandran M.P(L.S).
Construction of Building for Brothers Library and Reading Room-Puthenchantha at Panmana
Gramapanchayat in Chavara Constituency-General Electrical Work

SI No	Description of work	No. or Qty.	Unit	Rate	TOTAL AMOUNT	TOTAL AMOUNT in words
1	Electrification					
1.001	1.10.3 - Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required.Group C	9.000	point	1198.79	10789.11	Rupees Ten Thousand Seven Hundred Eighty Nine And Eleven paise Only
1.002	90.3.21.3 - Supply & installation of light fittings on 'C/U' shaped flat iron bracket
 Supply, conveyance, installation, testing and commissioning the light fittings of following types made from 0.5mm CRCA sheet complete with all accessories and lamps etc. directly on wall using 2 nos. 'C/U' brackets made from 20 x 3 mm MS flat, painting the flat iron bracket and giving connections with required length of 16/0.20mm 3 core copper conductor flex wire conforming to relevant ISS or extending the original wiring and giving connection etc. as required.1200 mm 1X20 W LED Lamp with box type fixture	1.000	each	1292.11	1292.11	Rupees One Thousand Two Hundred Ninety Two And Eleven paise Only
1.003	90.3.24.3 - Supply & installation of light fittings suspended on ball & socket arrangement with 19 mm down rod
 Supply, - conveyance, installation, testing and	2.000	each	1519.16	3038.32	Rupees Three Thousand Zero Thirty Eight And Thirty Two paise Only

Sl No	Description of work	No. or Qty.	Unit	Rate	TOTAL AMOUNT	TOTAL AMOUNT in words
	commissioning the light fittings of following types made of 5mm thick CRCA sheet accessories and lamps etc. including supplying and fixing ball and socket arrangements on PVC round block, suspension down rod of 19mm dia MS conduit up to 2x30cm length including painting and wiring the down rod with 16/0.20mm 3 core round copper conductor flex wire conforming to relevant ISS or extending the original wiring and giving connections etc. a required.1200 mm 1X20W LED Lamp with box type fixture					
1.004	OD23717/2024-2025 - Supply and fixing LED bulk head fitting having power consumption not more than 10W and light output less than 1100 Lumens with System efficacy>115 Lumen/Watt with premium quality diffuser for even distribution of light to wall/ceiling including giving connections with required length of 16/0.20mm PVC insulated and PVC sheathed 3 core round copper conductor flex wire conforming to relevant ISS or extending the original wiring and making good the surface as required.	2.000	each	567.44	1134.88	Rupees One Thousand One Hundred Thirty Four And Eighty Eight paise Only
1.005	90.15.4.1 - Supply Conveyance, installation, testing and commissioning of 20W LED street light output greater than 105lumen/W 4000-6000 K with IP 66 protection LED Chip make Cree/Lumileds/Nichea with power factor greater than 0.95 at full load, internal surge protection up to 8 KV, and Aluminium pressure die-cast Powder coated housing, acrylic cover complete with THD Less than 10%, power factor greater than 0.98, RoHS compliant, duly wired up for use on 230 V AC supply. Driver compartment should be separately accessible for maintenance (LM 79&80 certificates from NABL	1.000	each	2382.71	2382.71	Rupees Two Thousand Three Hundred Eighty Two And Seventy One paise Only

Sl No	Description of work	No. or Qty.	Unit	Rate	TOTAL AMOUNT	TOTAL AMOUNT in words
	accredited Third party lab to be produced mentioning chip manufacturer)					
1.006	90.3.18.1 - Supply, fabrication, conveyance and fixing the following sizes of B class GI pipe bent to shape / cut and welded to shape and fixing the same to wall / parapet using clamps as noted along with each size, painting with 2 coats of synthetic enamel paint over a coat of zinc chromate primer, making good the damages, colour washing etc as required. 25 mm dia with HG company fabricated clamps	1.200	metre	335.59	402.71	Rupees Four Hundred Two And Seventy One paise Only
1.007	90.4.5.4 - Supply, Installation, testing and commissioning of ceiling fan of following sizes including wiring the down rods of standard length (up to 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. as required. 1200mm sweep - ceiling fan complete with service valve minimum 4.0 (cubic meter/minute/Watt), Air delivery minimum 210(cubic meter/minute), Copper winding suitable for 230V/240V single phase AC supply	3.000	each	2206.97	6620.91	Rupees Six Thousand Six Hundred Twenty And Ninety One paise Only
1.008	1.25 - Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	3.000	each	414.06	1242.18	Rupees One Thousand Two Hundred Forty Two And Eighteen paise Only
1.009	1.17.3 - Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 3 X 1.5 sq.mm	20.000	metre	65.42	1308.40	Rupees One Thousand Three Hundred Eight And Forty Zero paise Only
1.010	1.17.29 - Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 2 x 6 sq. mm	8.000	metre	147.85	1182.80	Rupees One Thousand One Hundred Eighty Two And Eighty Zero paise Only
1.011	1.21.1 - Supplying and fixing of following sizes of medium	18.000	metre	101.15	1820.70	Rupees One Thousand Eight

23


Sl No	Description of work	No. or Qty.	Unit	Rate	TOTAL AMOUNT	TOTAL AMOUNT in words
	class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.20 mm					Hundred Twenty And Seventy Zero paise Only
1.012	1.21.2 - Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.25 mm	10.000	metre	109.50	1095.00	Rupees One Thousand Zero Ninety Five Only
1.013	90.12.7.2 - Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages, colour washing etc. as required.2 core 6 sq mm with factory made clamp	10.000	metre	200.97	2009.70	Rupees Two Thousand Nine And Seventy Zero paise Only
1.014	9.1.1 - Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.2 X 6 sq. mm (19mm)	2.000	set	239.69	479.38	Rupees Four Hundred Seventy Nine And Thirty Eight paise Only
1.015	1.31 - Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required. (For light plugs to be used in non residential buildings).	1.000	each	485.70	485.70	Rupees Four Hundred Eighty Five And Seventy Zero paise Only
1.016	1.24.1 - Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.5/6 amps switch	2.000	each	103.36	206.72	Rupees Two Hundred Six And Seventy Two paise Only
1.017	1.24.4 - Supplying and fixing following modular switch/ socket on the existing modular plate & switch	3.000	each	134.42	403.26	Rupees Four Hundred Three And Twenty Six paise Only

SI No	Description of work	No. or Qty.	Unit	Rate	TOTAL AMOUNT	TOTAL AMOUNT in words
	box including connections but excluding modular plate etc. as required.3 pin 5/6 amp socket outlet					
1.018	1.27.5 - Supplying and fixing following size/ modules. GI box alongwith modular base & cover plate for modular switches in recess etc as required.8 Module (125mmX125mm)	1.000	each	463.64	463.64	Rupees Four Hundred Sixty Three And Sixty Four paise Only
1.019	2.3.2 - Supplying and fixing following way. single pole and neutral. sheet steel. MCB distribution board. 240 V. on surface/ recess. complete with tinned copper bus bar. neutral bus bar. earth bar. din bar. interconnections. powder painted including earthing etc. as required. (But without MCBIRCCB/Isolator8 way. Double door	1.000	each	2131.61	2131.61	Rupees Two Thousand One Hundred Thirty One And Sixty One paise Only
1.020	2.14.2 - Supplying and fixing following rating. double pole. (single phase and neutral). 240 volts, residual current circuit breaker (RCCB). having a sensitivity current upto 300 milliamperes in the existing MCB DB complete with connections. testing and commissioning etc. as required.40 amps	1.000	each	2537.83	2537.83	Rupees Two Thousand Five Hundred Thirty Seven And Eighty Three paise Only
1.021	2.12.1 - Supplying and fixing following rating. double pole. 240 volts. isolator in the existing MCB DB complete with connections. testing and commissioning etc. as required.40 amps	1.000	each	410.04	410.04	Rupees Four Hundred Ten And Four paise Only
1.022	2.10.1 - Supplying and fixing 5 amps to 32 amps rating. 240/415 volts. "C" curve. miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections. testing and commissioning etc. as required.Single pole	4.000	each	241.57	966.28	Rupees Nine Hundred Sixty Six And Twenty Eight paise Only
1.023	5.4 - Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories. and providing masonry enclosure with cover plate having locking arrangement and watering	1.000	set	7529.02	7529.02	Rupees Seven Thousand Five Hundred Twenty Nine And Two paise Only

Sl No	Description of work	No. or Qty.	Unit	Rate	TOTAL AMOUNT	TOTAL AMOUNT in words
	pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.					
1.024	90.16.1.2 - Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required 2.65 mm copper conductor (12 SWG)	10.000	metre	44.93	449.30	Rupees Four Hundred Forty Nine And Thirty Zero paise Only
1.025	90.16.1.4 - Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required 4.00 mm copper conductor (8 SWG)	7.000	metre	98.63	690.41	Rupees Six Hundred Ninety Zero And Forty One paise Only
1.026	90.16.5.4 - Supply of superior quality copper earth socket for the following size of earth conductor including crimping etc. as required 4.00 mm (8 SWG)	4.000	each	27.95	111.80	Rupees One Hundred Eleven And Eighty Zero paise Only
1.027	90.16.5.2 - Supply of superior quality copper earth socket for the following size of earth conductor including crimping etc. as required 2.65 mm (12 SWG)	2.000	each	25.38	50.76	Rupees Fifty Zero And Seventy Six paise Only
1.028	90.16.2.1 - Supply and laying of the following sizes of B class GI pipe laid 0.6 m below ground level including excavating trench of suitable size and refilling etc, as required 15mm dia. GI pipe (medium class)	1.000	metre	192.16	192.16	Rupees One Hundred Ninety Two And Sixteen paise Only
1.029	OD 23949/2024-2025 - Supply and providing M8 anchor bolt hook in wall / parapet for binding support for service main	1.000	no	138.04	138.04	Rupees One Hundred Thirty Eight And Four paise Only
1.030	OD 23718/2024-2025 - Supply & installation of dust and vermin proof, wall mounting, Sintex meter box of size 430x215x150/120mm suitable for fixing KSEB meter, fuse units etc, hinged door construction for the front side with compartments if necessary, providing vision panel for the meter compartment, knock out for cable entry and exit (GSMB-4422) including 32A DP MCB, 32A cutout, N/L etc.	1.000	each	2776.40	2776.40	Rupees Two Thousand Seven Hundred Seventy Six And Forty Zero paise Only
1.031	OD 23716/2024-2025 -	1.000	L.S	2399.99	2399.99	Rupees Two

Sl No	Description of work	No. or Qty.	Unit	Rate	TOTAL AMOUNT	TOTAL AMOUNT in words
	Amount to be deposited with K.S.E.B for Meter testing/Availing service connection/Additional Load/Meter Shifting.(Actual amount will be reimbursed on production of original documents)					Thousand Three Hundred Ninety Nine And Ninety Nine paise Only
	Estimate PAC Rs.				56741.870	Rupees Fifty Six Thousand Seven Hundred Forty One And Eighty Seven paise Only
	Deduct cost of deptl.Materials				0.00	
	Tender variation of 0.0% below E/R				0.00	
	AGREED PAC Rs.				56741.87	Rupees Fifty Six Thousand Seven Hundred Forty One And Eighty Seven paise Only

The below work awarded to the contractor PRADEEP KUMAR.P,GGUPP4643E. at his quoted rate for 0.0% below estimate rate less cost of departmental material at a total agreed PAC 56742(Fifty Six Thousand Seven Hundred and Forty Two Only) as per the condition of the contract.


CONTRACTOR


ASSISTANT EXECUTIVE ENGINEER

EST_NO : PWD/BLDG/EST/7539/2024_6_1_1
BILL_NO : PWD/BLDG/EB/7539/2024_6_1_1-Final

K.P.W.FORM 23

GOVERNMENT OF KERALA PUBLIC WORKS DEPARTMENT

CE Office	:	Office of the Chief Engineer Buildings
Circle Office	:	Chief Electrical Engineer TVM
Division Office	:	Electrical Division Alappuzha
Sub Division Office	:	Electrical Sub Division Kollam
Section Office	:	Electrical Section II KLM

RUNNING ACCOUNT BILL

(For Contarctor:- The form provides for (r) Secured Advance and Payment for measured (works))

Cash Book Voucher No.	:	NILL
Name of Contractor	:	PRADEEP KUMAR.P
Name of Work	:	MP-LADS-2022-23, Work proposed by Sri. N.K Premachandran M.P(LS), Consruction of Building for Brothers Library and Reading Room-Puthenchantha at Panmana Gramapanchayat in Chavara Constituency- General Electrical Work
Serial No. of this bill	:	CC 1st & Final Bill
No.and Date of the previous bill of this work	:	NIL
Reference to agreement	:	93/AEE(ELE)2024-2025DATED 28-09-2024
Date of written order to Commence work	:	30-09-2024
Date of actual completion of work	:	01-10-2024

Digitally signed by Vishnu K Nair
Date:2024.10.01 12:46:38 +05:30

EST_NO : PWD/BLDG/EST/7539/2024_6_1_1
 BILL_NO : PWD/BLDG/EB/7539/2024_6_1_1-Final

Part-I Account of work Executed

MP-LADS-2022-23, Work proposed by Sri. N.K Premachandran M.P(LS), Construction of Building for Brothers Library and Reading Room-Puthenchantha at
Panmana Gramapanchayat in Chavara Constituency-General Electrical Work

Serial Number	As per estimate		As per agreement		Unit	Description of work done or supplies made	Quantities of work or supplies made		Value of agreement rate of work done or supplies made		Remarks
	Rate Rs	Number Qty. or weight	Rate Rs	Number Qty. or weight			Up to date	since last bill	Up to date Rs	since last bill Rs	
CC 1st & Final Bill											
Electrification											
1	1198.79	9.000	1198.79	9.000	point	1.10.3:Group C	9.000	9.000	10789.11	10789.11	
2	1292.11	1.000	1292.11	1.000	each	90.3.21.3:1200 mm 1X20W LED Lamp with box type fixture	1.000	1.000	1292.11	1292.11	
3	1519.16	2.000	1519.16	2.000	each	90.3.24.3:1200 mm 1X20W LED Lamp with box type fixture	2.000	2.000	3038.32	3038.32	

4	567.44	2.000	567.44	2.000	each	OD23717/2024-2025:Supply and fixing LED bulk head fitting having power consumption not more than 10W and light output less than 1100 Lumens with System efficacy>115 Lumen/Watt with premium quality diffuser for even distribution of light to wall/ceiling including giving connections with required length of 16/0.20mm PVC insulated and PVC sheathed 3 core round copper conductor flex wire conforming to relevant ISS or extending the original wiring and making good the surface as required.	2.000	2.000	1134.88	1134.88
5	2382.71	1.000	2382.71	1.000	each	90.15.4.1:Supply Conveyance, installation, testing and commissioning of 20W LED street light output greater than 105lumen/W 4000-6000 K with IP 66 protection LED Chip make Cree/Lumiled/Nichea with power factor greater than 0.95 at full load, internal surge protection up to 8 KV, and Aluminium pressure die-cast Powder coated housing, acrylic cover complete with THD Less than 10%, power factor greater than 0.98, RoHS compliant, duly wired up for use on 230 V AC supply. Driver compartment should be separately accessible for maintenance (LM 79&80 certificates from NABL accredited Third party lab to be produced mentioning chip manufacturer)	1.000	1.000	2382.71	2382.71
6	335.59	1.200	335.59	1.200	metre	90.3.18.1:25 mm dia with HG company fabricated clamps	1.500	1.500	503.39	503.39

7	2206.97	3.000	2206.97	3.000	each	90.4.5.4:Supply, Installation, testing and commissioning of ceiling fan of following sizes including wiring the down rods of standard length (up to 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. as required. 1200mm sweep - ceiling fan complete with service value minimum 4.0(cub meter/minute/Watt), Air delivery minimum 210(cubic meter/minute), Copper winding suitable for 230V/240V single phase AC supply	3.000	3.000	3.000	6620.91	6620.91	
8	414.06	3.000	414.06	3.000	each	1.25:Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	3.000	3.000	3.000	1242.18	1242.18	
9	65.42	20.000	65.42	20.000	metre	1.17.3.3 X 1.5 sq. mm	24.900	24.900	24.900	1628.96	1628.96	
10	147.85	8.000	147.85	8.000	metre	1.17.29:2 x 6 sq. mm	8.900	8.900	8.900	1315.87	1315.87	
11	101.15	18.000	101.15	18.000	metre	1.21.1:20 mm	22.500	22.500	22.500	2275.88	2275.88	
12	109.50	10.000	109.50	10.000	metre	1.21.2:25 mm	4.000	4.000	4.000	438.00	438.00	
13	200.97	10.000	200.97	10.000	metre	90.12.7.2:2 core 6 sq mm with factory made clamp	10.000	10.000	10.000	2009.70	2009.70	
14	239.69	2.000	239.69	2.000	set	9.1.1:2 X 6 sq. mm (19mm)	2.000	2.000	2.000	479.38	479.38	
15	485.70	1.000	485.70	1.000	each	1.31:Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required. (For light plugs to be used in non residential buildings).	1.000	1.000	1.000	485.70	485.70	
16	103.36	2.000	103.36	2.000	each	1.24.1:5/6 amps switch	2.000	2.000	2.000	206.72	206.72	
17	134.42	3.000	134.42	3.000	each	1.24.4:3 pin 5/6 amp socket outlet	3.000	3.000	3.000	403.26	403.26	
18	463.64	1.000	463.64	1.000	each	1.27.5:8 Module (125mmX125mm)	1.000	1.000	1.000	463.64	463.64	
19	2131.61	1.000	2131.61	1.000	each	2.3.2:8 way, Double door	1.000	1.000	1.000	2131.61	2131.61	

20	2537.83	1.000	2537.83	1.000	each	2.14.2.40 amps	1.000	1.000	1.000	2537.83	2537.83
21	410.04	1.000	410.04	1.000	each	2.12.1.40 amps	1.000	1.000	1.000	410.04	410.04
22	241.57	4.000	241.57	4.000	each	2.10.1:Single pole	4.000	4.000	4.000	966.28	966.28
23	7529.02	1.000	7529.02	1.000	set	5.4:Earthng with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	1.000	1.000	1.000	7529.02	7529.02
24	44.93	10.000	44.93	10.000	metre	90.16.1.2:2.65 mm copper conductor (12 SWG)	9.500	9.500	9.500	426.84	426.84
25	98.63	7.000	98.63	7.000	metre	90.16.1.4:4.00 mm copper conductor (8 SWG)	8.300	8.300	8.300	818.63	818.63
26	27.95	4.000	27.95	4.000	each	90.16.5.4:4.00 mm (8 SWG)	4.000	4.000	4.000	111.80	111.80
27	25.38	2.000	25.38	2.000	each	90.16.5.2:2.65 mm (12 SWG)	2.000	2.000	2.000	50.76	50.76
28	192.16	1.000	192.16	1.000	metre	90.16.2.1:15 mm dia. G.I pipe (medium class)	1.200	1.200	1.200	230.59	230.59
29	138.04	1.000	138.04	1.000	no	OD23949/2024-2025:Supply and providing M8 anchor bolt hook in wall / parapet for binding support for service main	1.000	1.000	1.000	138.04	138.04
30	2776.40	1.000	2776.40	1.000	each	OD23718/2024-2025:Supply & amp; installation of dust and vermin proof, wall mounting, Sintex meter box of size 430x215x150/120mm suitable for fixing KSEB meter, fuse units etc, hinged door construction for the front side with compartments if necessary, providing vision panel for the meter compartment, knock out for cable entry and exit(GSMB-4422) including 32A DP MCB, 32A cutout, N/L etc.	1.000	1.000	1.000	2776.40	2776.40
31	2399.99	1.000	2399.99	1.000	L.S	OD23716/2024-2025:Amount to be deposited with K.S.E.B for Meter testing/Availing service connection/Additional Load/Meter Shifting.(Actual amount will be reimbursed on production of original documents)	0.650	0.650	1559.99	1559.99	1559.99
Additional Components											

	TOTAL		56398.55		0.00	0	56398.55
	Secured Advance		0.00		0.00	0	0.00
	TOTAL		56398.55		0.00	0	56398.55
	Cost of Department Supply		0.00		0.00	0	0.00
	Cost of MR Component with in Extra Item		0.00		0.00	0	0.00
	TOTAL		56398.55		0.00	0	56398.55
	Tender Variation @ 0.000000%		0.00		0.00	0	0.00
	TOTAL		56398.55		0.00	0	56398.55
	Cost of Department Supply		0.00		0.00	0	0.00
	Cost of MR Component with in Extra Item		0.00		0.00	0	0.00
	TOTAL		56398.55		0.00	0	0.00
	Price Adjustment		0.00		0.00	0	56398.55
	Others		0.00		0.00	0	0.00
	Hand Receipt (HR)		0.00		0.00	0	0.00
	Mobilization Advance		0.00		0.00	0	0.00
	TOTAL		0.00		0.00	0	0.00
	Round off		56398.55		0.00	0	56398.55
	TOTAL BILL AMOUNT		0.45		0.00	0	0.45
	Applicable GST		56399.00		0.00	0	56399.00
	TOTAL including GST		10152.00		0.00	0	10152.00
	Centage Charges		66551.00		0.00	0	66551.00
	Contingency Charge		0.00		0.00	0	0.00
	Agency Charge		0.00		0.00	0	0.00
	Supervision Charge		0.00		0.00	0	0.00
	Quality Control Charge		0.00		0.00	0	0.00
	Work Establishment charge		0.00		0.00	0	0.00
	GRAND TOTAL		66551.00		0.00	0	66551.00

Recoveries

	Cost of Department Supply		0.00		0.00	0	0.00
	Central Goods and Service Tax (CGST) @ 1.000000%		564.00		0.00	0	564.00
	State Goods and Service Tax (SGST) @ 1.000000%		564.00		0.00	0	564.00
	Income Tax (IT) @ 1.000000%		564.00		0.00	0	564.00
	Workers Welfare Fund (WWF) @ 1.000000%		564.00		0.00	0	564.00
	Security Deposit (Retention Amount) @ 2.500000%		0.00		0.00	0	0.00
	Sales Tax		0.00		0.00	0	0.00
	GST on Sale		0.00		0.00	0	0.00
	Revenue		0.00		0.00	0	0.00

EST_NO : PWD/BLDG/EST/7539/2024_6_1
BILL_NO : PWD/BLDG/EB/7539/2024_6_1_1-Fi

Part II- Certificates and Signature

A. BILL PREPARATION SECTION

Certified that the measurements were made by me from **01-10-2024** to **01-10-2024** and are recorded on pages of measurement Book No **PWD/BLDG/MB/7539/2024_6_1_1** and that the work has been executed satisfactorily and that the bill as claimed above represents a correct accounts of contract's claims and liabilities.

Dated Signature of Officer preparing the bill.

Rank

അസിസ്റ്റന്റ് എക്സിക്യൂട്ടീവ്
പൊതുമരാമത്ത് വകുപ്പ്
വൈദ്യുതിവിഭാഗം സെക്ഷൻ-02,
കൊല്ലം-691001

B. REMARKS BY CHECK MEASURING OFFICER

certified that the item of work whose measurement
is recorded in pages to in M. Book
is 7539/24
1/10/24. The work done is satisfactory
and the Bill is claimed above represents
correct account of contractors contract

Sub Divisional Officer

ASSISTANT EXECUTIVE ENGINEER
ELECTRICAL WING SUB DIVISION
PWD KOLLAM

Divisional Officer

C. AUDIT SECTION

Checked again the calculations and verified the rates against the contract schedule, quantities against estimate provision and receipts and issue against sanctioned date.

Divisional Accountant

EST_NO : PWD/BLDG/EST/7539/2024_6_1_1
BILL_NO : PWD/BLDG/EB/7539/2024_6_1_1-Final

Part III- Memorandum of Payments

Figuers of abstract		Rs	Ps	Rs	Ps
	1 Total value of work done as per Part I Col II				
	2 Deduct amount with held -	66551	00	66551	00
	(a) From previous bill				
	(b) From this bill				
	3 Balance, i.e. up to date payments (1-2)K				
	4 Total amounts of payments already made as per entry (K) of Last running Account Bill No forwarded with accounts for	66551	00	66551	00
	5 Payments Now to be made as detailed below -				
	(a) By recovery of amounts creditable to this work				
	(i) Value of departmental materials or stock supplied and used as per column of Part IV material accounts of this bill				
	(ii).....				
	Total of item 2(b) and (a)(G)				
	By recovery of amounts creditable to other work, Heads of accounts etc.				
(i)	Hire on account of special Tools and plant issued to the contractor XXXIX.				
	Civil Works - Miscellaneous.				
(ii)	Recovery on accounts of Sales Tax-XIII				
(iii)	Other Taxes and Duties				
	1. Cost of Department Supply				
	2. Central Goods and Service Tax (CGST)	0	00	0	00
	3. State Goods and Service Tax (SGST)	564	00	564	00
	4. Income Tax (IT)	564	00	564	00
	5. Workers Welfare Fund (WWF)	564	00	564	00
	6. Security Deposit (Retention Amount)	564	00	564	00
	7. Sales Tax	0	00	0	00
	8. GST on Sale	0	00	0	00
	9. Revenue	0	00	0	00
	10. Security Deposit	0	00	0	00
	11. Centage Charges	0	00	0	00
	12. Contingency Charge	0	00	0	00
	13. Agency Charge	0	00	0	00
	14. Supervision Charge	0	00	0	00
	15. Quality Control Charge	0	00	0	00
	16. Work Establishment charge	0	00	0	00
	17. Royalty Mining and Geology	0	00	0	00
	18. Mobilization Secured Advance Recovery	0	00	0	00
	19. Fine and Penalty if any	0	00	0	00
	20. TOTAL DEDUCTIONS	113	00	113	00
(C)	By Cheque	2369	00	2369	00
	Tools 5 (b) and (c)(H)	64182	00	64182	00

The total up-to-date value of work is admitted for **Rupees Sixty Six Thousand Five Hundred Fifty One**
ICE (Printed On: 2024-10-01 12:46:28.523)

Only and after deducting the previous payments and including the amount with held, the bill is passed for **Rupees Sixty Six Thousand Five Hundred Fifty One Only** and that the work has been executed satisfactorily and that the bill as claimed above represents a correct accounts of contract's claims and liabilities.

Certified that the Bill as passed above has been ledgered Head Accountant	Officer authorising Payment	Dated Signature..... Rank..... Divisional Officer..... ASSISTANT EXECUTIVE ENGINEER ELECTRICAL WING SUB DIVISION DWI KOLLAM
---	-----------------------------------	---

Paid in cheque-- **64182.00** Paid in cash--**2369.00** Received Rupees (in words) **Rupees Sixty Six Thousand Five Hundred Fifty One Only** on account of this work (as a final payment is settlement of all demands).

Witness:-

Full Signature of Contractor

PRICE

Serial Number	Description of materials	Unit	Rates as in agreements	Quantity in hand as per last CC	Since receipt as per		Total in hand up to date	Since Issues		Balance in hand			Remarks		
					Divisional or General Store issue Note and Cash Book Voucher No.	This Bill		As per this bill	Value as per in rate col 4	Transferred to other works as per W.B.O	Total Issue	With Contractor		With Departmental Agencies	Total
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16

Note: Col-4 If materials not provided for in the agreements are issued vide paragraph 359 recovery will have to be made at the issued rate or market rate at the time of supply whichever may be greater and should include storage charges

Verified.....

Accountant

Officer Measuring the Work and

Signature:

Audit Section

12	13	14	15	16	Remarks
whichever may be greater and should include storage charges					

Signature: _____

അഡ്വക്കേറ്റ് എ.എ.എസ്. കാനക.

പൊതുമാതൃക "വകുപ്പ്"
 വൈദ്യുതിവിഭാഗം സെക്ഷൻ-02.

കോഡ്-691001

ഫോൺ : +91 7594975231

Signature of the _____

Contractor:

(at the time of payment)

Date:

Officer Measuring

the Work and

preparing the

bill:

.....Accountant

Audit Section